

STORM WATER ON-SITE DETENTION SYSTEM



Fast and Easy Installation
Increase Land Usage Area
Withstand High Vertical Loading
High Porosity
High Durability

Manufacture in Kuching, Sarawak

10 Years Products
Warranty



Manufactured by:

WENHONG PLASTIC INDUSTRIES SDN BHD

Lot 73, Block 45, 8th Mile, Batu Kitang Road, 93670 Kuching, Sarawak Malaysia Tel: 016-232 0831 Email: edenspheresdnbhd@gmail.com

Product's Specification







Side Cover



Top Cover

Product Name	MOVA Storm Water On-Site Detention System
Dimension	0.5m (L) * 0.5m (W) * 0.5m (D)
Weight	9kgs
Material	Virgin PP (Polypropylene Plastic)
Manning's Roughness, n	± 0.05
Vertical Loading	$30 \text{ tons/m}^2 \text{ (Ultimate load } \approx 87\text{kN)}$
Lateral Loading	10 tons/m^2
Void Ratio	95%

STANDARDS

- **SIRIM** Product Certification License.
- Fully Compliance with MASMA 2nd Edition, 2012 Design Standard.
- Fully Compliance with SUStoM
 Design Standard (DID Sarawak).

FLEXIBLE DESIGN

- Assembly numerous modular units into a storm water tank, cater for large volume requirement.
- Can work for both as on-site storage and subsurface drainage module.

High Durability

- Corrosion Resistance.
- UV & Chemical Resistance.

Aesthetic Value

- Fully covered, not exposed.
- Can have landscaping on top of the system.

Easy Replaceable & Cost Effective

- If a specific module damage (cracked or badly blocked), only required to replace the specific module.
- Super cost effective compared to other system that need to replace or clear the entire system when it is cracked or blocked.

One Stop Services & Maintenance

 In house professional engineer for technical support in planning, design, supply and install services for MOVA On-Site Detention System.

Application

- Under green area.
- Under **premix car park**.
- Suitable to be used as **subsoil** drainage system.

Installation Guideline

Excavate to the Required Depth.



300mm thick Foundation Treatment.



Backfilled with DCR at the side and the top of the system.



MOVA Storm Water On-Site Detention System installation including inlet, primary outlet and secondary outlet.

Connection Details

From Drainage System



 $\frac{MGPT_h/MGPT_c/Inspection}{Sump}$



MOVA Storm Water On-Site Detention System.



Discharge to Drainage System (External or Existing Drain System)

Maintenance

1. MOVA Gross Pollution Trap (Housing) [MGPTh]






Filtration Basket

- i. Remove access cover
- ii. Take out the filtration basket and remove the sediments **once a month** to ensure the efficiency.

2. MOVA Gross Pollution Trap (Commercial) [MGPTc]







- i. It is recommended to clear the large floatable pollutant at the filtration basket **once a month**
- ii. Remove of large volume of accumulated sediments, oil and grease using pump truck (if required) at **every 6 months** (recommended)

Sedimentation Control

Sedimentation unlikely to occur in the system as the **design of the system meets the** requirement of self-cleansing velocity. Additionally, MGPT act as filter to block the floatable pollutant and sediments. Moreover, the **geotextile used for wrapping the tank can filter off soil particles that smaller than 0.21mm.** Regular inspection or maintenance of the MGPT should be carried out to avoid blockage at the inlet of the system.

Project Reference

Location : Taman Fajar, Kota Kinabalu

Project Scope: The existing open pond been upgraded to MOVA Storm Water OSD System

Benefits :

i. Odorless
ii. Prevented Pest Breeding
iii. Increase Aesthetic Value
iv. Fully utilise Land Area
v. Easy Maintenance
iii. Environmental Friendly

The Existing size of RC Pond : 22m x 14m x 1m (308m³)

The Proposed size of MOVA OSD System : 22m x 13m x 1m (286m³)

Project Duration : 30 days

Before Installation



During Installation



After Installation







After 1 year



Project Reference (Con't)



Location : Kampung Bunga Rampai

Peoject Scope : Drainage & Detention System

Scope of work : 75m MOVA Drain

Size : $75m \times 0.5m \times 1m (37.50m^3)$

Project Duration : 40 days



Location : Kampung Haji Baki (Block A)

Peoject Scope : Drainage & Detention System

Scope of work : 270m MOVA Drain

Size : $270 \text{m x } 0.5 \text{m x } 1 \text{m } (135 \text{m}^3)$

Project Duration : 45 days



Location : IOT Senari

Project Scope : Drainage & Increase Land Usage (Modular System being used as carriageway)

Scope of work : 38m MOVA Drain

Size : $38m \times 0.5m \times 1m (19m^3)$

Project Duration: 10 days



Location : IBRACO Construction Sdn.

Bhd, 49 Units Shoplot

Peoject Scope : Detention System

Scope of work : 1,114m³ Detention System (4

units)

Duration : On Going

Technical Findings

1. ANALYSIS OF FLOW VELOCITY IN STORM WATER MODULE USING SOLID WORKS

Published by : Swinburne University of Technology Sarawak

Prepared by : Associate Professor Ts. Ir. Dr. Kelvin Kuok King Kuok

Major Findings:

Flow rate (m ³ /s)	1	2	3	4	5
Average Velocity (m/s)	0.18	0.21	0.36	0.41	0.51

The average velocity of water will be reduced to 10 to 20% of its initial velocity when it flow into MOVA On-Site Detention System. As the water need a longer duration to travel towards the discharge point, which enhanced the water retention/storage system. This is only possible with MOVA On-Site Detention System as it is the only system with reinforced columns in between to increase the friction coefficient thus restrict and reduce the velocity of water travelling in it, making it more effective in comparison with other detention system.

2. PERFORMANCE TEST FOR WEN HONG STORM WATER MODULE

Published by : University of Malaysia, UNIMAS

Prepared by : Dr. Charles Bong Hin Joo

Major Findings:

The MOVA storm water module has been found to have a **porosity of 95%** and **Manning's** \mathbf{n} value as ± 0.05

The MOVA storm water module has been found to be able to detain 35.2% to 95.6% of the total runoff generated by total rainfall which is equivalent to **5-min 10 year ARI** to **20-min 10 year ARI**.

3. Load Test Report

Published by : Curtin University Malaysia

Prepared by : Dr. Lee Yeong Huei

Major Findings:

Averagely, the module fail at **ultimate load of 87 kN** with deflection of 12.36 mm.

For lateral load test, the specimen failed at 19kN with deformation of 15mm.

Certificate



SIRIM QAS International Sdn. Bhd. (Company No.: 199601037981 (410334-X)) No.1, Persiaran Dato' Menteri, P.O.BOX 7035, Section 2, 40700 Shah Alam, Selangor Darul Ehsan, Malaysia Tel: 03-55445633 Fax: 03,55445886 www.sirim-qas.com.my

TEST REPORT

REPORT NO: 2020CB0731 PAGE: 1 OF 12

This Test Report refers only to samples submitted by the applicant to SIRIM QAS International Sdn. Bhd. and tested by SIRIM QAS International Sdn. Bhd. This Test Report shall not be reproduced, except in full and shall not be used for any purpose by any means or forms (including but not limited to advertising purposes) without written approval from the Chief Executive Officer, SIRIM QAS International Sdn. Bhd. Please refer the last page for Conditions Relating to the Use of Test Report.

THIS TEST REPORT IS ISSUED IN SECURED PDF SOFTCOPY

Applicant : WENHONG PLASTIC INDUSTRIES SDN. BHD

> Lot 73, Block 45, Jalan Batu Kitang, P.O Box 1603. 93732 Kuching, Sarawak.

Manufacturer : WENHONG PLASTIC INDUSTRIES SDN. BHD

Product : MOVA Stormwater Modular Tank

Reference Standard /

: i) Adopted to ASTM D2412 - 11 (2018) Method of Test

Standard Test Method for Determination of External Loading Characteristic of Plastic Pipe by Parallel Plate Loading.

ii) Adopted to ASTM F2418 - 19

Standard Specification for Polypropylene (PP) Corrugated Wall

Stormwater Collection Chambers

: Four (4) specimens were tested in vertical load and One (1) specimen of Description of sample

was tested in lateral load. All the testing was conducted at Curtin

Laboratory Malaysia.

Model: WT 500, Brand: MOVA

Nominal Size: 500 mm x 500 mm x 500 mm

Date Received of Complete Application : 29 September 2020

: J20201430581

Description of Test Results

: The test results of the submitted test samples are described in Page 2 to

12 of this test report.

Issued Date 20 November 2020

(MOHD HAFIZ BIN MOHD NA

Testing Executive

Approved Signatory;

pternationa

SECTION

CONSTRUCTION

DR SIHA BINTI RAJA ABDUL HANAN)

Head Civil & Construction Section Testing Services Department